

Employment Land Availability Assessment 2018

1	Foreword	3
2	What is an Employment Land Availability Assessment?	4
3	Targets & Lichfield District Context	6
4	Methodology	8
5	Summary of Potential Provision & Conclusions	14
A	ELAA Panel	18
B	Site Assumptions	20
C	Employment Land Completions	24
D	Schedule of all sites	31
E	Employment Land Availability Assessment Maps	?

1 Foreword

1.1 The Employment Land Availability Assessment (ELAA) is an evidence base and monitoring document which will be published annually as part of Lichfield District Council's suite of monitoring documents. The ELAA has a key role in identifying sites that have the potential for employment development and estimates their potential future capacity in terms of uses, floorspace and number of jobs. The ELAA also considers those sites which are allocated through the Lichfield District Local Plan and/ or have planning permission for employment uses. It is recognised that settlements evolve and land uses may change and therefore additional sites may become available in time. Therefore this is not a one-off document but a 'living' one which will be reviewed and updated.

1.2 This is the third edition of the ELAA for Lichfield District which covers the period from 1st April 2017 to 31st March 2018. The ELAA will be updated annually, alongside the [Strategic Housing Land Availability Assessment](#) (SHLAA), [Authority Monitoring Report](#) (AMR) and the [Five Year Housing Land Supply](#) document as part of the District Council's suite of monitoring documents.

1.3 The ELAA forms part of the evidence base for the production of the Local Plan. The policies and proposals within the Local Plan which cover employment development and the economy are based on many considerations, of which this assessment is only one.

ELAA Disclaimer

1.4 The inclusion of a site in this assessment **does not** indicate that it will be allocated or successfully obtain planning permission for any particular use. The ELAA is published with a view that it will be available alongside the Local Plan as part of its supporting evidence base. Similarly, the non-inclusion of a site in this study does not in any way preclude future development, providing it meets the planning policy framework that exists at the time a site comes forward.

2 What is an Employment Land Availability Assessment?

2.1 The National Planning Policy Framework (NPPF or the Framework) requires local planning authorities to prepare an ELAA to demonstrate that there are sufficient suitable sites to meet the identified needs for employment land within the District (NPPF paragraph 161). The ELAA should be used to establish realistic assumptions about the availability, suitability and likely economic viability of land within the plan period.

2.2 Land availability assessment guidance in relation to both employment and housing land is set out within the National Planning Practice Guidance (PPG). The PPG makes clear that ELAA's are a key component of the evidence base to support the delivery of sufficient land for economic development to meet those targets set out within the adopted Local Plan. The ELAA will be key to monitoring this target and the ongoing supply of land needed to achieve it. As such this ELAA will have the following five core outputs:

1	A list of all sites and broad locations assessed. Cross referenced to maps showing locations and boundaries of specific sites.
2	An assessment of each site or broad location identified for employment uses, in terms of its suitability for development, availability and achievability.
3	The potential type and quantity of employment use(s) that could be delivered on each identified site including an estimation of the number of jobs which could be delivered.
4	Constraints on the delivery of identified sites and any recommendations on how or when these could be overcome.
5	An assessment of the overall availability of employment land supply versus the identified needs.

2.3 The NPPF and PPG advocate the advantages of combining the land availability assessments for both economic and housing development. However, given the size of Lichfield District's SHLAA (over 1000 sites) it was considered that keeping the two documents separate, whilst using shared methodology, would ensure the documents are as user friendly as possible. Where sites are included in both the ELAA and SHLAA this will be cross referenced within the individual site assessments. It is intended that the two land availability assessments will be published alongside each other on an annual basis.

2.4 A thorough review of the SHLAA/ELAA methodology and format was undertaken in partnership with Cannock Chase District Council. This process has ensured that a broadly consistent methodology (whilst allowing for some local elaborations) is used across the authorities. This meets the requirements of the PPG and has been devised so each authority will share the methodology but still undertake and produce their own ELAA and SHLAA on an annual basis.

2.5 This assessment considers the availability of land for economic development within the 'B' Use Class as defined by the Use Classes Order. These are:

- B1(a) - Offices

- B1(b) - Research and development
- B1(c) - Light industry
- B2 - General Industry
- B8 - Storage and distribution

2.6 A draft version of the ELAA was made available to the Council's SHLAA/ELAA Panel for review prior to its wider publication. This Panel includes members of the development industry, local planning authorities and statutory consultees engaged in both housing and employment land developments. Further detail on the panel is included at Appendix A'ELAA Panel'.

2.7 This ELAA does not make judgements as to what the spatial strategy of the Local Plan should be nor does it allocate land for economic/employment development. It simply provides an indication of the land that could come forward for development and forms an evidence base for the Local Plan. Furthermore, the ELAA identifies land in all areas of the District, not just the main urban areas, in order to consider all potential sources of supply.

Data availability and baseline

2.8 The base date for the ELAA is the current monitoring year of 2017/ 2018. This includes completions from 2008-2018 (for schedule see Appendix C'Employment Land Completions' and sites with extant planning permission up to the end of March 2018. Lichfield District Council has undertaken further consultation related to its Local Plan Allocations (LPA) document within the monitoring year, the most recent closed on 19th February 2018. Any site submissions made through either the Call for Sites exercise or through consultation on the Local Plan up to the 1st April 2018 have been included within this assessment.

2.9 Lichfield District Council published an [Employment Land Capacity Assessment](#) (ELCA) in October 2016 as part of the evidence to support its emerging Local Plan. Information obtained through the ECLA with regards to sites has been considered and factored in to this edition of the document. A key aspect of the ECLA was to consider in detail the deliverability and availability of sites for employment development.

3 Targets & Lichfield District Context

3.1 The Lichfield District Local Plan Strategy was adopted on the 17th February 2015 and the spatial strategy for the District is set out within Core Policy 1 (The Spatial Strategy). In terms of employment the spatial strategy seeks to promote greater opportunities for high value employment within the District by providing a balanced portfolio of employment land to accommodate higher value employment opportunities serving both Lichfield and Burntwood and support for investment and redevelopment of older, well located, existing employment sites. Fradley will continue to be a focus for employment development. Core Policy 7 (Employment & Economic Development) sets out the requirement for 79.1 hectares of land of new and redeveloped employment land plus an additional 10 hectares to ensure flexibility will be provided to 2029. Such provision will aim to create between 7,310 and 9,000 additional jobs to achieve a job balance ratio of 85%. There is an emphasis on providing high-value jobs in business, education and research, those supporting a low carbon economy and other key growth sectors. The production of the ELAA is key to monitoring progress towards this target and the ongoing available supply of land to achieve it. The Lichfield District Local Plan Strategy allocated land for approximately 12 hectares of employment development within the Cricket Lane Strategic Development Allocation (SDA) with further allocations to be defined through the Local Plan Allocations document. There are separate targets for town centre uses (including office provision) which are not the explicit focus of this ELAA.

3.2 Policy Lichfield 3 (Lichfield Economy) states that Lichfield City will be the focus for new employment and office development with new employment uses focused close to existing employment sites. Policy Lichfield 3 and Policy Lichfield 6 (South of Lichfield) allocate approximately 12 hectares of land for employment development within the Cricket Lane Strategic Development Allocation (SDA). Policy Burntwood 3 (Burntwood Economy) seeks to maximise employment opportunities within Burntwood but also states that under-performing sites within the town will be considered through the Local Plan Allocations process. Policy Frad3 (Fradley Economy) states that Fradley will remain as a major focus for employment through the implementation of existing commitments and redevelopment of existing employment sites.

3.3 Lichfield District Council has been progressing the Local Plan Allocations document, with Regulation 19 consultation on the draft submission document closing on 19 February 2018. The emerging Local Plan Allocations document identifies proposed employment areas which will provide sufficient employment land to meet the requirements set out in Core Policy 7 with some flexibility which is to assist in the provision of approximately 6.5 hectares of employment land to meet the needs of Tamworth Borough. The Local Plan Allocations document was submitted of Examination in May 2018.

3.4 In addition to ongoing work on the Local Plan Allocations document, the District Council has begun work on a review of its Local Plan including consultation on the [Scope, Issues and Options](#) document between April and June 2018. This work will take place alongside the continuing work on the Local Plan Allocations document. The ELAA will form part of the supporting evidence base to both of these processes.

3.5 The National Planning Policy Framework and National Planning Practice Guidance require local authorities to produce land availability assessments for both economic/employment and housing land as part of the evidence base supporting their local plans. It is required to assess the existing and potential future supply of land to meet the identified needs.

3.6 As sites are completed, they are recorded through the annual monitoring and published within the Authority Monitoring Report (AMR) and recorded within the ELAA database. Completions since 2008 have been included within the assessment in a simple tabulated form at Appendix C and remain plotted on the mapping and detailed in the schedule of all sites (Appendix D) so that it is clear where development has taken place.

4 Methodology

4.1 This section sets out the methodology used for this assessment. The methodology has closely followed the guidance contained within the PPG and the agreed methodology being utilised by Lichfield District and Cannock Chase District Council.

Stage 1- Site/Broad Location Identification

4.2 The area of coverage for this ELAA is Lichfield District to enable monitoring against the Local Plan Strategy requirements. The PPG advocates that land availability assessments be produced to cover the functional economic market area which can be local planning authority areas. As set out at paragraph 2.4 the ELAA methodology will be used across the south-east Staffordshire councils with each authority carrying out the assessment within its own administrative boundaries.

4.3 Due to the 'manageable' number of submissions, there is no minimum threshold for the inclusion of a site in the assessment ⁽ⁱ⁾. However, there is a judgement to be made in terms of the contribution a particular development makes towards employment generation and land supply which may lead to smaller sites ultimately not being included e.g. those involving minor extensions/modifications to existing premises.

4.4 The PPG requires assessments to involve a number of key stakeholders. Both the ELAA and SHLAA use a joint-panel (across the local authorities) which consists of a number of stakeholders including; developers; those with land interests; land promoters; local property agents; partner organisations; Local Enterprise Partnerships; and business and business representative organisations. The Panel is convened each year and asked to consider the draft assessments prior to their publication. The Panel approach which has been adopted conforms with guidance within the PPG which suggests the involvement of a number of stakeholders in the land availability assessment process. Further detail regarding the Panel, including comments received can be found at [Appendix A](#).

4.5 The PPG states that the assessment should identify all sites and broad development locations regardless of the quantum of development needed. The ELAA methodology employed by Lichfield District Council has continued to identify sites from all sources in excess of the employment land requirements identified within the adopted Local Plan Strategy.

4.6 Lichfield District Council has held an ongoing 'Call for Sites' for the emerging Local Plan Allocations and Local Plan Review. This is an ongoing process which has been used to identify further sites for inclusion within the both the ELAA and SHLAA. The Call for Sites is open throughout the year and new submissions are included within the ELAA inline with the data baseline outlined at paragraph 2.8. In addition to the 'Call for Sites' there have been two formal consultations for the Local Plan Allocations document since the publication of the previous ELAA, any sites submitted through representations to either of these consultations have been included within this assessment.

4.7 All sites and schemes capable of assisting employment generation have therefore been initially considered including:

i The PPG recommends that sites of 0.25ha or developments of 500m² floorspace should be considered, but this is subject to local applicability

- Completions of employment generating development (since April 1st 2008 to 31st March 2017) (Table C.1'Employment Floor Space Completions 2008-2016');
- New land (previously not employment generating sites) and/or comprehensive redevelopment of previously employment generating sites (i.e. Demolition and rebuild);
- Units brought into employment uses from non-employment uses;
- Extension to existing premises (where these are not considered minor. See paragraph 4.3); and
- Refurbishment (including upgrade works, rebuilding/extensions) where former employment units/sites are being brought back into employment use after being vacant.

4.8 The following key data for sites was collected:

- Location including boundaries and site size (including Developable Area⁽ⁱⁱ⁾);
- Current/Previous land use;
- Likely proposed use;
- Likely number of jobs created⁽ⁱⁱⁱ⁾;
- Potential physical and environmental constraints; and
- Planning status (including information on planning application and current planning policy).

4.9 Table 4.1 sets out the key sources of information used in this assessment and which will be used for future updates when reviewing existing sites and identifying new ones. Sites can be broadly defined within two key groups; 'Sites within the planning process' and 'Sites not currently within the planning process'. Table 4.2 sets out the key data sources for ensuring information on these potential sites is up to date (up to 31st March 2018).

Table 4.1 Source of information

Sources of Information
Sites within the planning process: <ul style="list-style-type: none"> • Land allocated (or with permission) for employment land or other land uses which are no longer required for those uses; • Sites proposed to be allocated through emerging development plan documents;

ii The standard definition of 'Developable Area' is the amount of land available for development, including on site landscaping and infrastructure. Where information has not been provided the Lichfield District Employment Land Review (ELR) 2012 has been used to provide estimations of the floorspace which could be provided.

iii Where this information was not provided the assumptions in terms of job density have been taken from the Homes & Communities Agency Employment Density Guide (3rd Edition) November 2015

Sources of Information
<ul style="list-style-type: none"> • Unimplemented/outstanding planning permission for employment use; • Sites with planning permissions for employment use that are under construction; • Sites where planning permission has previously been refused for employment development; and • Sites where a planning application has been submitted but is not yet determined.
<p>Sites not currently within the planning process:</p> <ul style="list-style-type: none"> • Vacant/derelict land and buildings (of appropriate size for economic/employment development); • Surplus public sector land; • Additional employment opportunities in established employment areas; • Additional sites proposed by stakeholders through 'Call for Sites' process and/or through Local Plan representations; • Sites considered within the Lichfield District Employment Land Review (ELR) 2012 where these are considered to be in the 'B' use classes (not including Town centre B uses).

Table 4.2 ELAA data sources

ELAA data sources
<ul style="list-style-type: none"> • Planning permissions/applications determined by 31/03/18 (where relevant and available detail will be given of development progress) ; • Commencement and completion records to 31/03/18 (site visits and Local Authority Building Control records); • National register of Public Sector Land; • Local Authority Empty Property Register; • Commercial Property Databases; • Ongoing site specific representations from stakeholders; • Local knowledge from planning and other officers and property agents; and • Other desktop sources of information e.g. Property agent websites.

4.10 Upon completion of this stage a refreshed, up to date list of all potential sites was available to then assess further in stage 2.

Stage 2 - Site/broad location assessment

4.11 Site assessment work for economic/employment uses will be undertaken in accordance with the methodology outlined within the PPG. The development potential of sites will be considered according to their suitability, availability and achievability.

4.12 In terms of the developable area of sites (including estimates floorspace), the likely breakdown of uses within a site and the potential number of jobs created the following assumptions will be applied:

- Sites with planning permission will use the permitted floorspace and estimated job creation where provided;
- If the information submitted alongside a site includes a layout, and additional information in terms of floorspace and jobs this will be assessed and used where it is considered appropriate; and
- For other sites the assumptions contained within the Lichfield District Council [Employment Land Review](#) (ELR) 2012 for calculating floorspace and the split of uses on site. The CLG Employment Density Guide (3rd Edition) November 2015 will be used to estimate the number of jobs to be created created (see Appendix B'Site Assumptions' for detail on site assumptions).

4.13 It is then necessary to categorise the sites according to their development potential in order to set out a clear picture of the supply. There is no set method for this within the NPPF or PPG in terms of employment land so Lichfield District Council have chosen to use locally determined categories drawn on guidance within the PPG. The NPPF provides clear categories for housing sites (deliverable/developable) and the Lichfield District SHLAA then includes a category for 'Not Developable' sites for those sites falling outside of other categories but does not provide such detail in relation to employment land. Drawing upon this, the Council will categorise sites within the ELAA within two categories. Sites will be categorised as either 'Available' or 'Not Available'. By applying this distinction a clear picture of the type and quantity of land 'available' in the short to medium term will be presented. This category is broadly equivalent to both the deliverable and developable categories within the SHLAA. Land currently identified as 'not available' may be appropriate to meet longer term needs, or if the identified constraints could be overcome they could potentially serve to meet needs in the medium to longer term. The 'Not Available' category will also include sites that are unlikely to be suitable in the longer term (Green Belt designation, isolated sites etc). This category is broadly equivalent to the 'Not Developable' category within the SHLAA.

4.14 'Available' land for employment uses will consist of sites which have been assessed as follows:

- A suitable location for employment development. Suitability can be affected by the a number of factors, for example: development plan policy, market interest, physical problems, infrastructure issues (including proximity to transport nodes), potential impacts and environmental conditions. Where there are no major concerns in relation to the aforementioned factors then a site can be considered suitable. Where a site is proposed

to be allocated through the emerging Local Plan Allocations document it has been considered to represent a suitable location for development. Should changes be made to the emerging plan this could need to be reviewed in future editions of the ELAA.

- Site is available for the type of development being proposed (sites which are being proposed/promoted for changes of use away from employment land would not be considered available) and is in an achievable location for the development. The assessment of availability has been informed by the landowner/agent where they have indicated the site could be developed. Information collected through the ECLA has assisted with this aspect of the ELAA.
- A site is considered to be achievable where there is a reasonable prospect that the site will be developed at a particular point in time. For sites that have outstanding planning permission/allocation it is assumed that the development will be brought forward unless the applicant/owner/agent advises the District Council otherwise. Intelligence from individual applicants/agents/owners will be taken account of where this is available. The PPG requires sites potential viability to be considered as part of its achievability. Given the large number of sites within the ELAA and SHLAA documents it is not possible or practicable to test viability on individual sites. As part of the evidence to support the Community Infrastructure Levy (CIL) the District Council has commissioned a significant body of evidence which has been the subject of independent examination. This evidence concludes that employment development is not currently viable on a speculative nature within the District. However, it is noted that across the plan period it is expected that markets will change and such development may become viable.

4.15 All other sites are then classified as 'Not Available' at present. Sites will be reconsidered on an annual basis and where additional information has been submitted. As such it is possible and indeed likely that sites may move between categories between editions of the ELAA. Where sites are within the Green Belt these will be identified within the same categories but will be highlighted on the maps as being within the Green Belt. It should also be noted that certain sites may be 'uncategorised' within the assessment. Such an assessment will only be used where there are a number of uncertainties about the availability, achievability and deliverability which prevent the assessment from concluding that a site should fall into either of the two categories (Available/Not Available).

4.16 The employment land target is for non town centre B class uses^(iv). As such the focus of this assessment is upon land outside of these centres which are more suited to accommodating other B class uses. However, local planning policy recognises that it will be difficult to accommodate all town centre uses (specifically office provision) within the town centres potentially necessitating the use of out of centre sites. Therefore a category of potential town centre office sites is included within the ELAA. The monitoring of town centre developments more generally is included within the Authority Monitoring Report.

iv The Local Plan Strategy includes policies which identify targets for town centre uses, including office provision, to be located within the identified town centres

Stage 3: Assessment and Final Evidence Base

Please note that this stage corresponds to stages 4 and 5 of the methodology advocated within the PPG. PPG Stage 3 (Windfall Assessment) is not considered appropriate for the ELAA.

4.17 The assessment methodology provides for a review of the findings of the assessment. Its purpose is to consider the refined site assessments and the identified supply being assessed against the requirements of the Local Plan.

4.18 This assessment concludes that there is currently around 102 hectares of available employment land within the District. A large majority of this land is either under construction or has the benefit of an extant planning permission. In addition to this there has been completion of approximately 50 (gross) hectares of employment land since 2008.

4.19 The size of available sites ranges from less than one hectare to those in excess of 13 hectares with the most commonly available sites within a 2-5 hectare range. The largest sites are those remaining at East Hill, Fradley Park and Burton Old Road, Streethay. Many of the larger available sites would also be capable of being subdivided into separate development parcels which provides even greater flexibility for potential end users within the employment land supply. The available land supply is considered to be flexible with a large majority being available for a range of B1/B2/B8 uses.

4.20 There is approximately 166 hectares of land which has been classified as 'not available' at present which consists of 69 hectares of sites located within the Green Belt. In addition to the land assessed as 'Not Available' is the Rugeley Power Station site which is categorised as 'uncertain' within this assessment.

4.21 Section 5 of the document provides the detailed conclusions and summary of the potential provision of employment land. This represents the final evidence base stage of the methodology which has been summarised in the paragraphs above.

Monitor & Review

4.22 The preparation and publication of a ELAA enables a clear base for the future monitoring of employment land provision against the requirements set out within the Local Plan. This is the second edition of the ELAA which is a living document and will be continually updated and published annually. Additional sites (or any changes to sites) will be added to the ELAA database on submission to Lichfield District Council and where such information means the inclusion of a new site assessment or amendments to existing assessments this will be contained within subsequent publications of the document.

4.23 The ELAA will be updated annually (with data complete to the end of the most recently concluded financial year). Previous editions of the ELAA will remain available so that progress of the supply and sites can be viewed across documents.

5 Summary of Potential Provision & Conclusions

ELAA Results (PPG Stage 5: Final Evidence Base)

5.1 In total 120 sites (including completed sites) have been identified and assessed through the process. Table 5.1 summarises the conclusions of the assessment and details the employment land supply position in Lichfield District at 31/03/2018. This shows the completions which have been recorded within the District within the plan period and also the supply of 'Available' sites which includes those sites currently under construction, with the benefit of extant planning permission and those sites outside of the planning process which are assessed as being 'Available' including sites within allocated employment areas. For completeness included in the results is the 'Not Available' sites.

Table 5.1 Employment Land Supply - 'Available' sites

Completions 2017-2018	Uses	Ha (net)	Floorspace (m ²) (net)
Completions 2017-2018 (Appendix C'Employment Land Completions')	Total	16.53 (15.65)	62,954 (61,139)
	B1/B2/B8	16.53 (15.65)	62,254 (61,139)
	B1a (Offices)	0	0
Completions 2008-2018	Uses	Ha (net)	Floorspace (m ²) (net)
Completions 2008-2018 (Appendix C'Employment Land Completions')	Total	50.16 (30.89)	158,198 (100,0164)
	B1/B2/B8	48.29 (29.02)	143,306 (85,972)
	B1a (Offices)	1.867 (1.867)	14,192 (14,192)
'Available' Supply (2018-2029)	Uses	Ha	Floorspace (m ²)
Sites currently under construction (Table D.1'Sites with planning permission')	Total	13.1	23,879
	B1/B2/B8	12.98	23,699
	B1a (Offices)	0.12	180
Sites with planning permission (Table D.1'Sites with planning permission')	Total	45.80	174,527
	B1/B2/B8	45.80	174,527
	B1a (Offices)	0	0
Available sites (Appendix D'Schedule of all sites')	Total	43.54	140,077
	B1/B2/B8	43.54	140,077
	B1a (Offices)	0	0

Completions 2017-2018	Uses	Ha (net)	Floorspace (m ²) (net)
Total 'Available Supply'	Total	102.44	338,483
	B1/B2/B8	102.44	338,483
	B1a (Offices)	It should be noted that a majority of to above supply is available for B1/B2/B8 uses and as such could contribute toward specific B1a office supply.	

Table 5.2 Employment Land Supply - 'Not Available' sites

Sites 'Not Available'	Uses	Ha	Floorspace (m ²)
Sites assessed as 'Not Available'	Total	166.28	677,377
	B1/B2/B8	97.16	337,041
	B1a (Offices)	0.26	2594
	B1/B2/B8 - Sites within Green Belt	68.86	337,742
	B1a (Offices) - Sites within Green Belt	0	0

5.2 Table 5.1 demonstrates that there is currently approximately 102 hectares of 'Available' employment land within Lichfield District. This is alongside the 50 (gross) hectares of land which has already been completed within the District. The ELAA 2018 identifies that there is currently sufficient supply of available employment land to meet the target set within the Local Plan Strategy. Trends indicate that B2 and B8 developments have been the most common place within Lichfield District with a much smaller number of B1 schemes being completed. In terms of B1a offices, these have predominantly been small scale save for two developments during 2008 and 2009.

5.3 There is a mixture of available sites in terms of size, location and potential employment use. The supply is made up of a range of sites a majority of which are Brownfield sites within the Districts existing industrial areas. The supply should be kept under review to ensure continued availability of sites sufficient to meet the Local Plan targets. If a shortfall in supply is identified then additional sites may need to be identified and brought forward where they are required and appropriate.

Appendices

ELAA Panel

Appendix A ELAA Panel

A.1 The PPG advocates that land availability assessments (ELAA/SHLAA) should be prepared in partnership with key stakeholders. This should include developers, local property agents, local communities and other agencies who should be involved from the outset.

A.2 Cannock Chase District and Lichfield District Councils determined to set up a joint SHLAA/ELAA Panel which built upon the success of earlier panels employed by the Council's. The SHLAA/ELAA Panel were consulted on the draft methodology and will be consulted on each edition of the SHLAA/ELAA. Its remit will be to consider the methodology and the detailed approach to site assessment, as set out within section 4 of this document.

A.3 The Panel comprised representatives from the local authorities, local agents, developers and others with property interest/knowledge within the area. The Panel comprised:

- Representatives from the three south-east Staffordshire authorities: Lichfield District Council, Cannock Chase District Council and Tamworth Borough Council;
- Developers - representatives including St Modwen, Persimmon Homes and Bromford Housing Group;
- Representatives from planning consultants active in the local area including CT Planning, Pegasus Group and Barton Wilmore;
- Representatives from the land promotion sector including First City, Richborough Estates, Jones Lang Lasalle (JLL), Kingstons CPC;
- Representatives from the Statutory Consultees; and
- Representatives from other Local Plan Authorities including South Staffordshire District Council and Stafford Borough Council.

A.4 The specific terms under which the Panel operated were agreed by the panel and defined as:

- To assist in the production of a robust SHLAA and ELAA for the Councils by helping to achieve agreement on the methodology;
- To share information and intelligence on market conditions and viability in relation to housing and employment developments;
- To consider and give advice on the findings of the assessments undertaken by the councils and to help come to a view on suitability, deliverability and developability of sites including consideration of site constraints;
- To act as an independent body that is representative of key stakeholders/sectors for the sole purpose of the preparation of the LAA's; and
- To undertake any other tasks agreed with the Panel for the purpose of preparing the LAA reports.

A.5 Copies of the Panel Terms of Reference and representations received during the panel consultation can be made available on request.

Site Assumptions

Appendix B Site Assumptions

B.1 The following section outlines the assumptions used when calculating the split of uses, total floorspace, and job density for sites within the ELAA. These assumptions are used when such information is not provided for a site (see paragraphs 4.8 and 4.12 of the main body of this report).

B.2 There are three main areas where assumptions are made through this report which utilise two sources of evidence as illustrated in table B.1 below. Please note that the Job Density assumptions within the Lichfield District Council Employment Land Review (ELR) 2012 were based upon the Employment Density Guide (2nd Edition) 2010 which has now been superseded. This ELAA will use the latest data available.

Table B.1

Assumption	Evidence Source
Split of uses on site	Lichfield District Council Employment Land Review (ELR) 2012
Total floorspace	
Job density	Employment Density Guide (3rd Edition) November 2015 - Homes & Communities Agency

Split of land uses

B.3 Table B.2 sets out the assumptions used when determining the split of employment uses on a site. Where an indicative split of land uses is not provided then the assessment considers likely mixture of uses based on a number of factors, such a site size and mix of adjacent uses.

Table B.2 Split of land uses (source Lichfield District Council ELR 2012 page 95)

Typology	Split of Land Uses		
	B1	B2	B8
B1 city centre	100%	0%	0%
B1	100%	0%	0%
B1/B2	50%	50%	0%
B1/B8	20%	0%	80%
B1/B2/B8	33%	33%	33%
B1/B2/B8s	10%	45%	45%
B2	0%	100%	10%
B2/B8	0%	50%	50%
B8	0%	0%	100%

Total floorspace

B.4 Table B.3 provides the plot ratio assumptions used to determine the likely floorspace to be provided where only site size is available.

Table B.3 Plot ratio assumptions (source Lichfield District Council ELR 2012 page 130)

Land use class	Average plot ratio (m ² per hectare)
B1a/B1b	3,250
B1c/B2	3,500
B8	4,000

Employment Density

B.5 Table B.4 provides the assumption used when calculating the likely number of jobs that could be created through the development of a site. This job density is in essence the number of jobs per square metre of development.

Table B.4 Employment density matrix (source HCA Employment Density Guide (3rd Edition) November 2015 page 29)

Use class	Sub-category	Sub-sector	Density (m ²)	Notes	LDC density assumption (m ²) ^(v)
B1a Offices	General Office	Corporate	13	NIA	12 (unless detail is provided of B1a use it is assumed B1b & b1c)
		Professional Services	12	NIA	
		Public Sector	12	NIA	
		TMT	11	NIA	
		Finance & Insurance	10	NA	
	Call Centres		8	NIA	N/A
B1b	R&D Space		40-60	NIA lower densities will be achieved in units with higher provision of shared or communal spaces.	40
B1c	Light Industrial		47	NIA	
B2	Industrial & Manufacturing		36	GIA	
B8	Storage & Distribution	National Distribution Centre	95	GEA	80
		Regional Distribution Centre	77	GEA	

v used where detail of useclass is not provided

Use class	Sub-category	Sub-sector	Density (m ²)	Notes	LDC density assumption (m ²) ^(v)
		'Final Mile' Distribution Centre	70	GEA	
Mixed B Class	Small Buisness Worksapce	Incubator	30-60	B1a, B1b - the density will relate to balance between spaces, as the share of B1a increases so to will employment densities.	N/A
		Marker Spaces	15-40	B1c, B2, B8 - Differences between 'planned space' density and utilisation due to membership model.	N/A
		Studio	20-40	B1c, B8	N/A
		Co-working	10-15	B1a - Difference between 'planned space' density and utilisation due to membership model.	N/A
		Managed Workspace	12-47	B1a, B1b, B1c	N/A
B8/Sui Generis	Data Centres	Wholesale	200-950		N/A
		Wholesale Dark Site	440-1,400		N/A
		Co-location Facility	10-540		N/A

v used where detail of useclass is not provided

Employment Land Completions

Appendix C Employment Land Completions

Table C.1 Employment Floor Space Completions 2008-2016

ELAA ID	ELR ID	SHLAA ID	Planning Application Reference	Site Address	Area (ha)	Use Class	Floorspace complete	Net?
2008-2009								
59	E25	-	06/00062/FULM	Council Deport, Plant Lane, Burntwood	1.05	B1/B8	600	Yes
6	E7	-	06/00308/FULM	City Wharf, Davidson Road, Lichfield	0.5	B1a	5,000	Yes
57	E5	-	06/01000/FULM	Greenhough Road, Lichfield	0.2	B1a	5,300	Yes
TOTAL							10,900	
2009-2010								
TOTAL							0	-
2010-2011								
60	E6/P5	-	08/01271/FULM	Former Revelan (Integra Works), Eastern Avenue, Lichfield	4.52	B2	5,510	No
TOTAL							5,510	
2011-2012								
40	E13	-	11/00231/COU	Unit 26C, Burntwood Business Park, Zone 3, Burntwood	0.08	B1/B2/B8	283.5	No
38	-	-	11/01051/COU	Kingsbury Pallets, Units 1&2 Burton Road, Streethay	1.7	B2	1,359	No
24	-	-	10/01242/FUL	Martin & Field Unit 3, Eastern Avenue, Lichfield	0.24	B2/B8	1,367	Yes
TOTAL							3009.5	

ELAA ID	ELR ID	SHLAA ID	Planning Application Reference	Site Address	Area (ha)	Use Class	Floorspace complete	Net?
2012-2013								
7	P7	-	12/00937/COU	Land west of Burton Old Road, Lichfield	0.6	B8	74	Yes
66	-	-	11/00619/COU	3 Jervis Court, Rugeley Road, Burntwood	0.001	B1a	139	Yes
64	-	-	09/00837/FUL	Mount Villa, 2 Trent Valley Road, Lichfield	0.18	B1a	164	Yes
65	-	-	12/00524/COU	Access Bookings, 30 St John Street, Lichfield	0.1	B1a	315	Yes
28	-	-	06/00816/COU	Croxall hall, Barn A, Croxall	0.16	B1a	375	Yes
23	-	-	11/00981/COU	Unit 7a Burntwood Business Park, Zone 2	0.05	B1/B2/B8	500	No
48	E43	-	12/01362/COU	Units 5a & 5b, Burntwood Business Park, Zone 2	0.1	B1/b2/B8	543	No
51	E12	-	13/00105/COU	Unit 3a, Burntwood Business Park, Zone4	0.13	B2/B8	757	No
49	-	-	12/01294/COU	Packington Moor Farm, Jerrys Lane	0.25	B8	760	Yes
55	E13	-	13/00197/COU	Unit 17, Burntwood Business Park, Zone 3	0.5	B2/B8	806	No
53	E12	-	13/00092/COU	Unit 4a, Burntwood Business Park, Zone 4	0.17	B2/B8	1,304	No
52	E12	-	13/00095/COU	Unit 4b, Burntwood Burntwood	0.17	B2/B8	1,391	No

ELAA ID	ELR ID	SHLAA ID	Planning Application Reference	Site Address	Area (ha)	Use Class	Floorspace complete	Net?
				Business Park, Zone 4				
50	E12	-	13/00106/COU	Unit 4, Burntwood Business Park, Zone 4	0.19	B2/B8	1,554	No
54	E12	-	13/00093/COU	Unit 2, Burntwood Business Park, Zone 4	0.4	B2/B8	2,034	No
33	-	-	12/00600/COU	Former Dale Joinery, Britannia Way	0.94	B8	3,760	No
45	E12	-	12/01340/COU	Unit 5, Burntwood Business Park, Zone 4	1.06	B2/B8	5,993	No
44	E13	-	12/00996/COU	Unit 25, Burntwood Business Park	1.76	B1/B2/B8	6,784	No
TOTAL							27,253	
2013-2014								
74	-	-	13/01088/COU	Cherry Orchard, land off, Lichfield	0.1	B8	400	Yes
39	E43	-	14/00905/FULM	Martin & Field Unit 11, Eastern Avenue, Lichfield	0.11	A1/B1c/B8	628	Yes
21	E42	-	09/00414/FULM	Birchbrook Industrial Park, Lynn Lane, Shenstone	0.5	B8	1,300	No
27	E1	-	10/00438/COU	Former Swan Fleet Hire, Burton Road, Streethay	0.7	B2	1,496	No
34	E33	-	12/00458/COU	Unit 5, Dive Close, Fradley (Faurecia)	1.3	B2/B8	5,113	No

ELAA ID	ELR ID	SHLAA ID	Planning Application Reference	Site Address	Area (ha)	Use Class	Floorspace complete	Net?
31	E37	-	11/01305/FULM	Hanger 5, Gorse Lane, Fradley (Roxanne)	2.6	B2/B8	7,456	Yes
TOTAL							16,393	
2014-2015								
73	-	-	14/01087/COU	19b The Close, Lichfield	0.02	B1a	86	Yes
70	E4	-	14/00061/COU	Trent Business Centre, Eastern Avenue, Lichfield	0.01	B1b	112.6	No
68	-	-	14/00710/COU	Former Decades Boutique, 22 St John Street, Lichfield	0.006	B1a	180	Yes
25	-	-	10/01269/COU	Shenstone Park farm, Park Lane, Little Hay	3.07	B1	306.42	No
71	-	643	14/00429/COU	The Olde Corner House, Muckley Corner	0.05	B1a	485	Yes
65	-	-	12/00524/COU	Access Bookings, 30 St John Street, lichfield	0.1	B1a	586	UYes
69	E6, P5	40	14/00963/COU	Unit 1c Eastern park, Eastern Avenue, Lichfield	0.08	B2	757	No
62	-	260	13/00136/FUL	Former St Josepys Presbytery, New Street, Chasetown, Burntwood	0.08	B1a	847	Yes
31	E37	719	11/01305/FULM	Hanger 5, Gorse Lane, Fradley (Roxanne)	2.6	B2/B8	6,089	Yes
42	E32	-	12/00833/FULM	Unit 7, Blenheim Way, Fradley Park, Fradley	3.21	B2/B8	11209.7	No
TOTAL							20658.72	

ELAA ID	ELR ID	SHLAA ID	Planning Application Reference	Site Address	Area (ha)	Use Class	Floorspace complete	Net?
2015-2016								
22	-	891	10/00145/COU	RJK Construction, Overly Lane, Alrewas	0.15	B1a	115	Yes
35	-	733	11/00374/COU	Pool House, Dam Street, Lichfield	0.09	B1a	139	Yes
78	P29	-	15/01372/COU	Shaw Lane Farm, Shaw Lane, Kings Bromley	0.1	B8	175	Yes
29	-	183	11/01319/FULM	31a Sandford Street, Lichfield	0.08	B1a	201	Yes
61	E19	-	13/00063/COU	Midwest Motor, Unit 1, Trent Valley trading Estate	0.08	B8/A1	340	No
75	-	-	15/00067/FUL	Orica Building, Fisherwick Road, Fisherwick	0.38	B2	367	Yes
43	E19	-	12/01052/FUL	Units 9 & 11, Trent Valley Trading Estate	0.1	B1c	600	Np
76	-	-	15/00377/COU	Former Go Banannas, Smiths Close, Burntwood Business Park, Zone 3	0.24	B1b	830	Yes
63	E25	-	13/00701/COU	Unit 4, Burntwood Business Park, Zone 1	0.8	B2/B8	1,753	No
TOTAL							4,520	
2016-2017								
77	-	-	14/00897/COU	Units A & B, Main Street, Alrewas	0.2	B8	2103	No
79	-	-	15/00500/FULM	Unit 20, Burntwood Business Park	1.09	B8	4060	No

ELAA ID	ELR ID	SHLAA ID	Planning Application Reference	Site Address	Area (ha)	Use Class	Floorspace complete	Net?
				Zone 3m Cinder Road, Burntwood				
46	-	-	15/01114/COU	Land north of Britannia Park, Lichfield	0.55	B8	213	Yes
80	-	-	14/01059/FUL	Land at RJK, Overlay Lane, Alrewas	0.15	B1a	260	Yes
31	-	-	16/00820/FULM	Roxanne UK Ltd, Hanger 5, Fradley Airfield. Wood End Lane	0.03	B1c	364	Yes
TOTAL							7,000	
2017-2018								
11	P11	-	16/00585/FULM & 16/00586/FULM	Land at Easthill, Wood End Lane, Fradley	12.7	B8	51,279	Yes
46	-	-	15/01114/COU	Land north of Britannia Park, Lichfield	0.55	B8	260	Yes
119	-	-	17/01327/FULM	Former Ash & Lacey pressings, Lynn Lane, Shenstone	0.88	B2/B8	1815	No
96	-	-	15/01196/COU	Levesley Group HQ, Rykneild House	2.4	B8	9600	Yes
TOTAL							62,954	

Schedule of all sites

Appendix D Schedule of all sites

Table D.1 Sites with planning permission

ELAA ID	Location	Source	Planning Application No.	Site Area (Ha)	Floorspace (m ²)	Proposed use class	ELAA Category	ELAA Map Ref (Appendix E'Employment Land Availability Assessment Maps')
8	Land east of Burton old Road, Lichfield	Planning Permission Full	14/00799/REMM (18/00648/FULM - currently under determination)	13.68	38,191	B1/B2/B8	Available	Map 3: Lichfield City (East)
10	Former Lucas site, Wood End Lane, Fradley	Planning Permission Full	17/00276/FULM	5.2	21,367	B1/B8	Available	Map 2: Fradley Park
11	Land at East Hill, Fradley	Under Construction	16/00585/REMM & 16/00586/REMM	11.9	30,228	B1/B2/B8	Available	Map 2: Fradley Park
17	Land north of Wood End Lane, Fradley Park	Planning permission Full	10/01403/REMM (Initial works have taken place - permission therefore extant due to initial implementation)	4.2	9,290	B8	Available	Map 2: Fradley Park
18	Land at Halifax Close, Fradley Park	Planning permission Full		10.9	44,585	B8	Available	Map 2: Fradley Park
67	Land at Lichfield South Business Park, Birmingham Road	Planning Permission Full	14/00395/OUTM, 16/01426/REMM, 17/01277/REMM & 17/01787/REMM	4.79	11,500	B1/B2	Available	Map 21: Wall Island
82	Land off Cinder Road, Burentwood Business Park Zone 3, Burntwood	Under Construction	17/01100/FULM	0.8	2795	B1/B2/B8	Available	Map 1: Burntwood Business Park
84	Land off Cannel Road,	Planning Permission Full	16/00821/FULM	0.82	4646 (net 2430)	B2/B8	Available	Map 1: Burntwood Business Park

ELAA ID	Location	Source	Planning Application No.	Site Area (Ha)	Floorspace (m ²)	Proposed use class	ELAA Category	ELAA (App E'Er Land Avail Ass Map
	Burntwood Business Park Zone 3							
97	Land at Easthill, Fradley (2)	Planning Permission Full	17/00059/FULM	5.5	32,894	B8	Available	Map Park
114	New Farm, Park Lane, Elmhurst, Lichfield	Under Construction	16/00430/FUL	0.12	180	B1a	Available	Map Lane
115	Unit 41 Trent Valley Trading Estate, Station Road, Rugeley	Planning Permission Full	16/01102/FUL	0.23	560	B2	Available	Map Valle Esta
116	Former HSS Hire, Station Road, Lichfield	Under Construction	17/00816/COU	0.12	420	B2	Available	Map City
117	Mile Oak Far, Plantation Lane, Mile Oak	Planning Permission Outline	17/00806/OUTM	0.48	1100	B1/B8	Available	Map Faze Oak
118	Land adjacent Unit 18 Burntwood Business Park Zone 3, Cinder Road, Burntwood	Under Construction	17/00989/FUL	0.16	650	B2/B8	Available	Map Burn Buis

D.1 The individual site assessments are provided in numerical order (ELAA ID).

Table D.2 Land north of Plan Lane, Burntwood Business Park Zone 1

ELAA ID: 1	Location: Land north of Plant Lane, Burntwood Business Park Zone 1		Settlement: Burntwood	Ward: Chase Terrace
SHLAA ID: N/A	ELR site ID: P1	Planning Ref: N/A	Source: Allocated	Proposed use class: B1/B2/B8

ELAA ID: 1	Location: Land north of Plant Lane, Burntwood Business Park Zone 1		Settlement: Burntwood	Ward: Chase Terrace
Site Area (Ha): 1.7	Floorspace (m ²): 6047	FTE Jobs (estimate): 133	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of SSSI. Within Forest of Mercia area. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area. Adjacent to residential area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. Promoted by landowner/agent for employment uses. ELCA notes that land owners confirms site is available for employment development.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.3 Land south of Cannock Road, Burntwood Business Park Zone 1

ELAA ID: 2	Location: Land south of Cannock Road, Burntwood Business Park Zone 1		Settlement: Burntwood	Ward: Chase Terrace
SHLAA ID: N/A	ELR site ID: P2	Planning Ref: Planning permission for B1/B2 expired	Source: Allocated	Proposed use class: B1/B2
Site Area (Ha): 0.15	Floorspace (m ²): 472	FTE Jobs (estimate): 26	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of SSSI. Within Forest of Mercia area. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area. Adjacent to residential area. ELCA notes that land owner confirms site is available for employment development and planning application to be submitted within 5 years.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. Promoted by landowner/agent for employment uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.4 Land east of Miners Way , Burntwood Business Park Zone 1

ELAA ID: 3	Location: Land east of Miners Way, Burntwood Business Park Zone 1		Settlement: Burntwood	Ward: Chasetown
SHLAA ID: N/A	ELR site ID: P3	Planning Ref: N/A	Source: Allocated	Proposed use class: B1/B2
Site Area (Ha): 0.2	Floorspace (m ²): 675	FTE Jobs (estimate): 37	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	

ELAA ID: 3	Location: Land east of Miners Way, Burntwood Business Park Zone 1	Settlement: Burntwood	Ward: Chasetown
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of SSSI. Within Forest of Mercia area. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area. Adjacent to residential area.		
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. Promoted by landowner/agent for employment uses.		
Achievable? Yes	Achievability Notes: No known constraints to achievability.		
ELAA Category: Available			

Table D.5 Davidson Road (City Wharf), Lichfield

ELAA ID: 4	Location: Davidson Road (City Wharf), Lichfield		Settlement: Lichfield	Ward: St Johns
SHLAA ID: 759	ELR site ID: P4	Planning Ref: N/A	Source: Allocated	Proposed use class: B1a
Site Area (Ha): 0.41	Floorspace (m ²): 1334	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 4: Lichfield City (Central)	
Suitable? Yes	Suitability Notes: Recently redeveloped for residential use (Complete SHLAA 2016).			
Available? No	Availability Notes: Recently redeveloped for residential use (Complete SHLAA 2016).			
Achievable? No	Achievability Notes: Recently redeveloped for residential use (Complete SHLAA 2016).			
ELAA Category: Not Available				

Table D.6 Former Revelan Works, Eastern Avenue, Lichfield

ELAA ID: 5	Location: Former Revelan Works, Eastern Avenue, Lichfield		Settlement: Lichfield	Ward: Curborough
SHLAA ID: 39	ELR site ID: P5	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 3.1	Floorspace (m ²): 12,080	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 6: Lichfield City (North)	
Suitable? Yes	Suitability Notes: Within Lichfield which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of BAS. Adjacent to area of flood risk. Site is within the Cannock Chase SAC zone of influence. Within designated Lichfield City Neighbourhood Area. Adjacent to residential areas. Site proposed to be removed from employment area and allocated for residential development through emerging Local Plan Allocations document.			
Available? No	Availability Notes: Site currently under construction for residential development following grant of permission at appeal. ELCA notes site is not available following grant of planning permission for residential development. Site therefore not considered to be available for employment/economic development.			
Achievable? No	Achievability Notes: Not to be developed for employment uses following grant of residential permission which is now under construction.			

ELAA ID: 5	Location: Former Revelan Works, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Curborough
ELAA Category: Not Available			

Table D.7 Land north of Britannia Business Park, Lichfield

ELAA ID: 6	Location: Land north of Britannia Business Park , Lichfield		Settlement: Lichfield	Ward: Boley Park
SHLAA ID: N/A	ELR site ID: P6	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 1.17	Floorspace (m²): 4193	FTE Jobs (estimate): 90	ELAA Map Ref (Appendix E): Map 6: Lichfield City (East)	
Suitable? Yes	Suitability Notes: Within Lichfield which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Greenfield site. Grade 2 agricultural land. TPO protected trees adjacent to site. Site is within the Cannock Chase SAC zone of influence. Within designated Lichfield City Neighbourhood Area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. Adjacent part of site currently under construction for employment use.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.8 Land west of Burton old Road, Lichfield

ELAA ID: 7	Location: Land west of Burton Old Road, Lichfield	Settlement: Lichfield	Ward: Boley Park
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.9 Land east of Burton old Road, Lichfield

ELAA ID: 8	Location: Land east of Burton Old Road, Lichfield	Settlement: Lichfield	Ward: Boley Park
ELAA Category: Planning Permission Full (see Table D.1 & Map 3: Lichfield City (East))			

Table D.10

ELAA ID: 9	Location: Land at Rugeley Power Station		Settlement: Other Rural	Ward: Armitage with Handsacre
SHLAA ID: 173	ELR site ID: P9	Planning Ref: 03/00624/OUTM	Source: Allocated	Proposed use class: B1/B2/B8 (mixed use)
Site Area (Ha)3.3	Floorspace (m²): 11,777	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 10: Armitage with Handsacre	
Suitable? Yes	Suitability Notes: Site is located within the East of Rugeley Strategic Development Allocation (SDA) to provide employment . Part of larger cross boundary site which includes land within Cannock Chase District. Site is adjacent to built up area of Rugeley within Cannock Chase District. Site is adjacent to Rugeley Power Station site which has no closed for power generation. Grade			

ELAA ID: 9	Location: Land at Rugeley Power Station	Settlement: Other Rural	Ward: Armitage with Handsacre
	3 agricultural land classification. Site is within the Cannock Chase SAC zone of influence. Within designated Armitage with Handsacre Neighbourhood Area. Likely site would be part of wider redevelopment of the Power Station site (see ELAA site 109).		
Available? Unsure	Availability Notes: Power station has closed. Decommissioning and demolition/remediation expected to take approximately 4 years from closure of station. Timescales and level of demolition/remediation prior to development currently unknown. Site is likely to come forward as part of wider redevelopment however mix/scale of uses and timescales currently unknown. ELCA assessed site as uncertain. Given information it is unsure as to the potential use/mix of uses to be proposed for the site.		
Achievable? Yes	Achievability Notes: Given uncertainty of the timescales of the site becoming available there is uncertainty over the achievability of the site. It is noted that developers consider the redevelopment of the site within plan period possible.		
ELAA Category: Uncategorized - not enough information currently to categorise site as either 'available' or 'not available'. Site is likely to become available for development within the plan period, however the mix/scale of development and timescales are currently unknown. As such floorspace not included in results of assessment at this stage.			

Table D.11 Wood End Lane, Fradley Park

ELAA ID: 10	Location: Wood End Lane, Fradley park	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Planning Permission Full (see Table D.1 & Map 2: Fradley Park)			

Table D.12 Land at East Hill, Fradley

ELAA ID: 11	Location: Land at East Hill, Fradley	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Under Construction (see Table D.1 & Map 2: Fradley Park) - 12.7ha or 51,279m ² completed 2017/18			

Table D.13 Wellington Crescent, Fradley Park (1)

ELAA ID: 12	Location: Wellington Crescent, Fradley (1)		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P12	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 2.3	Floorspace (m²): 7475	FTE Jobs (estimate): 120	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? Yes	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. ELCA notes that land owner confirms site is available for employment development intention to submit planning application.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			

ELAA ID: 12	Location: Wellington Crescent, Fradley (1)	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Available			

Table D.14 Wellington Crescent, Fradley Park (2)

ELAA ID: 13	Location: Wellington Crescent, Fradley (2)		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P13	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 0.6	Floorspace (m²): 2150	FTE Jobs (estimate): 75	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? Yes	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.15 Site 14: Wellington Crescent, Fradley Park (3)

ELAA ID: 14	Location: Wellington Crescent, Fradley (2)		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P14	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 0.4	Floorspace (m²): 1397	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? Yes	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? No	Availability Notes: Site currently available and is allocated for employment use. ELCA notes that land owner suggests change of use application will be pursued to provide additional car parking.			
Achievable? No	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.16 Wellington Crescent, Fradley Park (4)

ELAA ID: 15	Location: Wellington Crescent, Fradley (4)		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P15	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8

ELAA ID: 15	Location: Wellington Crescent, Fradley (4)		Settlement: Fradley	Ward: Alrewas & Fradley
Site Area (Ha): 0.3	Floorspace (m²): 1075	FTE Jobs (estimate): 42	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? Yes	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? No	Availability Notes: Site currently available and is allocated for employment use.			
Achievable? No	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.17 Wellington Crescent, Fradley Park (5)

ELAA ID: 16	Location: Wellington Crescent, Fradley (5)		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P16	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 0.26	Floorspace (m²): 860	FTE Jobs (estimate): 34	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? Yes	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. ELCA notes that land owner confirms site is available for employment development intention to submit planning application.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.18 Land north of Wood End Lane, Fradley Park

ELAA ID: 17	Location: Land north of Wood End Lane, Fradley Park	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Planning Permission Outline (see Table D.1 & Map 2: Fradley Park) NB - site is listed as Planning permission full however agent/owner has confirmed that ground works were commenced several years ago which constitute start on site and therefore permission is extant.			

Table D.19 Land at Halifax Close, Fradley Park

ELAA ID: 18	Location: Land at Halifax Close, Fradley Park	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Planning Permission Outline (see Table D.1 & Map 2: Fradley Park) NB - site is listed as Planning permission full however agent/owner has confirmed that ground works were commenced several years ago which constitute start on site and therefore permission is extant.			

Table D.20 Land at Halifax Avenue, Fradley Park

ELAA ID: 19	Location: Land at Halifax Avenue, Fradley Park		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: 426	ELR site ID: P19	Planning Ref: 10/01403/REMM	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 16.6	Floorspace (m²): 56206	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? No	Suitability Notes: Within Fradley park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within Strategic Development Allocation (SDA) for residential development within the adopted Local Plan Strategy. Previously allocated for employment use. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. Site is within 1km of BAS. Adjacent to area of flood risk. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area. Adjacent to residential areas.			
Available? No	Availability Notes: Site is allocated for residential development within adopted Local Plan Strategy.			
Achievable? No	Achievability Notes: Unlikely to be developed for employment uses following allocation for residential development within adopted Local Plan Strategy.			
ELAA Category: Not Available				

Table D.21 Land south of Auction Centre, Fradley Park

ELAA ID: 20	Location: Land south of Auction Centre, Fradley Park		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P20	Planning Ref: -	Source: Allocated	Proposed use class: B2/B8
Site Area (Ha): 3.80	Floorspace (m²): 13,545	FTE Jobs (estimate): 332	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? Yes	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.22 Former Industrial Instruments building, Lynn Lane, Shenstone

ELAA ID: 21	Location: Former Industrial Instruments building, Lynn Lane, Shenstone	Settlement: Shenstone	Ward: Shenstone
ELAA Category: Complete (see Appendix C & Map 7: Shenstone)			

Table D.23 RJK Construction, Overly Lane

ELAA ID: 22	Location: RJK Construction, Overly Lane	Settlement: Rural	Ward: Alrewas & Fradley
ELAA Category: Complete (see Appendix C & Map 11: Overly Lane)			

Table D.24 Former GKN site, Trent Valley Road, Lichfield

ELAA ID: 23	Location: Former GKN site, Trent Valley Road, Lichfield		Settlement: Lichfield	Ward: Boley Park
SHLAA ID: 835	ELR site ID: E4	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 2.4	Floorspace (m²): 8600	FTE Jobs (estimate): 183	ELAA Map Ref (Appendix E): Map 3: Lichfield City (East)	
Suitable? Yes	Suitability Notes: Within Lichfield which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within the Cannock Chase SAC zone of influence. Within designated Lichfield City Neighbourhood Area. Site proposed to be removed from employment area through emerging Local Plan Allocations document.			
Available? No	Availability Notes: Site currently available and is allocated for employment use. Site being marketed for employment development opportunities. ELCA notes that site has been promoted for alternative schemes and land owner has stated alternative development scheme likely to be pursued.			
Achievable? No	Achievability Notes: No known constraints to achievability. May require demolition.			
ELAA Category: Not Available				

Table D.25 Martin & Field No 3, Eastern Avenue, Lichfield

ELAA ID: 24	Location: Martin & Field No 3, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Stowe
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.26 Shenstone Park Farm, Park Lane, Little Hay

ELAA ID: 25	Location: Shenstone Park Farm, Park Lane, Little Hay	Settlement: Lichfield	Ward: Bourne Vale
ELAA Category: Complete (see Appendix C & Map 7: Shenstone)			

Table D.27 Units 6 - 10, Mile Oak Business Centre

ELAA ID: 26	Location: Units 6-10, Mile Oak Business Centre		Settlement: Fazeley	Ward: Fazeley
SHLAA ID: N/A	ELR site ID: -	Planning Ref: 10/01447 (expired)	Source: Expired planning permission	Proposed use class: B2
Site Area (Ha): 0.3	Floorspace (m²): 290	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 8: Fazeley, Mile Oak & Bonehill	

ELAA ID: 26	Location: Units 6-10, Mile Oak Business Centre	Settlement: Fazeley	Ward: Fazeley
Suitable? Yes	Suitability Notes: Site adjacent to Fazeley which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within Green Belt. Brownfield site, possibility for contaminated land. Grade 2 agricultural land. BAS within 1km.		
Available? No	Availability Notes: Planning permission expired. No evidence development is being pursued.		
Achievable? No	Achievability Notes: No known constraints to achievability.		
ELAA Category: Not Available			

Table D.28 Former Swan Fleet Hire, Burton Road, Lichfield

ELAA ID: 27	Location: Former Swan Fleet Hire, Burton Road, Lichfield	Settlement: Lichfield	Ward: Whittington & Streethay
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.29 Barn A, Croxall Hall, Croxall Road

ELAA ID: 28	Location: Barn A, Croxall Hall, Croxall Road	Settlement: Rural	Ward: Mease Valley
ELAA Category: Complete (see Appendix C & Map 12: Croxall Road)			

Table D.30 Land adjacent 31a Sandford Street, Lichfield

ELAA ID: 29	Location: Barn A, Croxall Hall, Croxall Road	Settlement: Rural	Ward: Mease Valley
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Centre))			

Table D.31 Lonkhill Farm, Ashby Road

ELAA ID: 30	Location: Lonkhill Farm, Ashby Road		Settlement: Rural	Ward: Mease Valley
SHLAA ID: N/A	ELR site ID: -	Planning Ref: 10/00496 (expired)	Source: Expired planning permission	Proposed use class: B1/B2/B8
Site Area (Ha): 0.9	Floorspace (m²): 3225	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 13: Ashby Road	
Suitable? Yes	Suitability Notes: Site is outside of recognised settlement in rural area. Greenfield site. Agricultural buildings. Grade 2 agricultural land.			
Available? No	Availability Notes: Planning permission expired. No evidence development is being pursued.			
Achievable? No	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.32 Gorse Lane & Wood End Lane, Roxanne, Fradley

ELAA ID: 31	Location: Gorse Lane & Wood End Land, Roxanne, Fradley	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Complete (see Appendix C & Map 2: Fradley Park)			

Table D.33 Lyalvale Express, Express Estate, Fisherwick

ELAA ID: 32	Location: Laylvale Express, Express Estate, Fisherwick		Settlement: Rural	Ward: Whittington & Streethay
SHLAA ID: N/A	ELR site ID: -	Planning Ref: 11/00248 (expired)	Source: Expired planning permission	Proposed use class: B2
Site Area (Ha): 0.16	Floorspace (m²): 1605	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 14: Fisherwick	
Suitable? Yes	Suitability Notes: Site is outside of recognised settlement in rural area. Greenfield site. Grade 2 agricultural land. TPO protected trees within site. Within Whittington & Fisherwick Neighbourhood Area.			
Available? No	Availability Notes: Planning permission expired. No evidence development is being pursued.			
Achievable? No	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.34 Former Dale Joinery, Britannia Way, Lichfield

ELAA ID: 33	Location: Former Dale Joinery, Britannia Way, Lichfield	Settlement: Fradley	Ward: Boley Park
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.35 Unit 5, Dove Close, Fradley

ELAA ID: 34	Location: Unit 5, Dove Close, Fradley	Settlement: Fradley	Ward: Ailrewas & Fradley
ELAA Category: Complete (see Appendix C & Map 2: Fradley Park)			

Table D.36 Pool House, Dam Street, Lichfield

ELAA ID: 35	Location: Pool House, Dam Street, Lichfield	Settlement: Lichfield	Ward: Stowe
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.37 Unit 7A, Burntwood Business Park Zone 2

ELAA ID: 36	Location: Unit 7A, Burntwood Business Park Zone 2	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.38 Site 37: Birmingham Road, Shenstone Wood End

ELAA ID: 37	Location: Birmingham Road, 176, Shenstone Woodend		Settlement: Lichfield Wood End (other rural)	Ward: Little Aston & Stonall
SHLAA ID: 912	ELR site ID: -	Planning Ref: 11/00959/COU	Source: Expired	Proposed use class: B1

ELAA ID: 37	Location: Birmingham Road, 176, Shenstone Woodend		Settlement: Lichfield Wood End (other rural)	Ward: Little Aston & Stonall
Site Area (Ha): 0.16	Floorspace (m²): 293	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 15: Birmingham Road	
Suitable? Yes	Suitability Notes: Outside of settlement within the rural area. Greenfield site. Within Green Belt. Agricultural land classification Grade 3. TPO protected trees within site. BAS within 1km.. Within designated Little Aston Neighbourhood Area. Adjacent to residential areas.			
Available? No	Availability Notes: Site has permission for residential development which has been implemented. Employment permission expired.			
Achievable? No	Achievability Notes: Unlikely to be developed for employment uses following grant of residential permission.			
ELAA Category:	Not Available			

Table D.39 Units 1-2 Burton Road, Streethay, Lichfield

ELAA ID: 38	Location: Units 1-2 Burton Road, Streethay, Lichfield	Settlement: Lichfield	Ward: Whittington & Streethay	
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City East)				

Table D.40 Martin & Field unit 11, Eastern Avenue, Lichfield

ELAA ID: 39	Location: Martin & Field Unit 11, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Stowe	
ELAA Category: Complete (see Appendix C & Lichfield City East)				

Table D.41 Unit 26c, Ring Road, Burntwood Business Park Zone 3, Burntwood

ELAA ID: 40	Location: Unit 26c Ring Road, Burntwood Business Park Zone 3, Burntwood	Settlement: Burntwood	Ward: Chasetown	
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)				

Table D.42 Fazeley Saw Mills, Lichfield Street, Fazeley

ELAA ID: 41	Location: Fazeley Saw Mills, Lichfield Street, Fazeley		Settlement: Fazeley	Ward: Fazeley
SHLAA ID: 96	ELR site ID: -	Planning Ref: 12/00775 (expired)	Source: Expired planning permission	Proposed use class: B1c
Site Area (Ha): 0.4	Floorspace (m²): 144	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 8: Fazeley, Mile Oak & Bonehill	
Suitable? Yes	Suitability Notes: Site within Fazeley which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Part of site within Flood Zone 2. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Within Conservation Area. Adjacent to listed building.			
Available? No	Availability Notes: Planning permission expired. No evidence development is being pursued.			
Achievable? No	Achievability Notes: No known constraints to achievability.			

ELAA ID: 41	Location: Fazeley Saw Mills, Lichfield Street, Fazeley	Settlement: Fazeley	Ward: Fazeley
ELAA Category: Not Available			

Table D.43 Unit 7, Blenheim Way, Fradley Park

ELAA ID: 42	Location: Unit 7, Blenheim Way, Fradley Park	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Complete (see Appendix C & Map 2: Fradley Park)			

Table D.44 Unit 9-11 Trent Valley Trading Estate

ELAA ID: 43	Location: Unit 9-11, Trent Valley Trading Estate	Settlement: Rural	Ward: Colton & the Ridwars
ELAA Category: Complete (see Appendix C & Map 16: Trent Valley Trading Estate)			

Table D.45 Unit 25 Burntwood Business Park, Burntwood

ELAA ID: 44	Location: Unit 25 Burntwood Business Park, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.46 Unit 5 Burntwood Business Park Zone 4, Burntwood

ELAA ID: 45	Location: Unit 5 Burntwood Business Park Zone 4, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.47 Land north of Britannia Park, Britannia Way (2)

ELAA ID: 46	Location: Land north of Britannia Park, Britannia Way (2)	Settlement: Lichfield	Ward: Boley Park
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.48 Triangle, Burntwood Business Park Zone 4, Burntwood

ELAA ID: 47	Location: Triangle at Burntwood Business Park Zone 4		Settlement: Burntwood	Ward: Chasetown
SHLAA ID: 1122	ELR site ID: P30	Planning Ref: N/A	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 3.17	Floorspace (m²): 11288	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of SSSI. Within Forest of Mercia area. Possible area of Coal subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area. Adjacent to Burntwood Strategic Development Allocation (SDA). Adjacent to town centre boundary. Site proposed to be removed from employment area and allocated for residential development through emerging Local Plan Allocations document.			

ELAA ID: 47	Location: Triangle at Burntwood Business Park Zone 4	Settlement: Burntwood	Ward: Chasetown
Available? No	Availability Notes: Planning permission on site for residential development (Ref:16/00666/OUTM & 17/01484/REMM).		
Achievable? No	Achievability Notes: Unlikely to be developed for employment uses following grant of residential permission (subject to legal agreement).		
ELAA Category: NotAvailable			

Table D.49 Unit 5a & 5b Burntwood Business Park Zone 2, Burntwood

ELAA ID: 48	Location: Unit 5a & 5b Burntwood Business Park Zone 2, Burntwood	Settlement: Lichfield	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.50 Packington Moor Farm, Jerrys Lane

ELAA ID: 49	Location: Packington Moor Farm, Jerrys Lane	Settlement: Rural	Ward: Bourne Vale
ELAA Category: Complete (see Appendix C & Map 17: Jerrys Lane)			

Table D.51 Unit 4, Burntwood Business Park Zone 4, Burntwood

ELAA ID: 50	Location: Unit 4, Burntwood Business Park Zone 4, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.52 Unit 3a, Burntwood Business Park Zone 4, Burntwood

ELAA ID: 51	Location: Unit 3a, Burntwood Business Park Zone 4, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.53 Unit 4b, Burntwood Business Park Zone 4, Burntwood

ELAA ID: 52	Location: Unit 4b, Burntwood Business Park Zone 4, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.54 Unit 4a, Burntwood Business Park Zone 4, Burntwood

ELAA ID: 53	Location: Unit 4a, Burntwood Business Park Zone 4, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.55 Unit 2, Burntwood Business Park Zone 4, Burntwood

ELAA ID: 54	Location: Unit 2, Burntwood Business Park Zone 4, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.56 Unit 17, Burntwood Business Park Zone 3, Burntwood

ELAA ID: 55	Location: Unit 17, Burntwood Business Park Zone 3, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.57 City Wharf, Lichfield

ELAA ID: 56	Location: City Wharf, Lichfield	Settlement: Lichfield	Ward: St Johns
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.58 Greenhough Road, Lichfield

ELAA ID: 57	Location: Greenhough Road, Lichfield	Settlement: Lichfield	Ward: Leomansly
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.59

ELAA ID: 58	Location: Land at Greenhough Road (Remainder), Lichfield		Settlement: Lichfield	Ward: Leomansley
SHLAA ID: 1102	ELR site ID: P19	Planning Ref: 13/00809/FULM	Source: Expired	Proposed use class: B1a
Site Area (Ha): 0.26	Floorspace (m²): 2594	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 4: Lichfield City (Central)	
Suitable? No	Suitability Notes: Within Lichfield which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Adjacent to conservation area. Site is within the Cannock Chase SAC zone of influence. Within designated Lichfield City Neighbourhood Area. Adjacent to residential areas. Site proposed to be removed from employment area and allocated for residential development through emerging Local Plan Allocations document.			
Available? No	Availability Notes: Site is currently under construction for residential development. Site therefore not considered to be available for employment/economic development.			
Achievable? No	Achievability Notes: Unlikely to be developed for employment uses following implementation of permission for residential development.			
ELAA Category: Not Available				

Table D.60 Council Depot, Plant Road

ELAA ID: 59	Location: Council Depot, Plant Road	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.61 Former Integra, Eastern Avenue, Lichfield

ELAA ID: 60	Location: Former Integra, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Curborough
ELAA Category: Complete (see Appendix C & Map 6: Lichfield City (North))			

Table D.62 Unit 1, Trent Valley Trading Estate

ELAA ID: 61	Location: Unit 1, Trent Valley Trading Estate	Settlement: Rural	Ward: Colton & the Ridwares
ELAA Category: Complete (see Appendix C & Map 16: Trent Valley Trading Estate)			

Table D.63 Former St Josephs, New Street, Burntwood

ELAA ID: 62	Location: Former St Josephs, New Street, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.64 Unit 4, Burntwood Business Park Zone 1, Burntwood

ELAA ID: 63	Location: Unit 4, Burntwood Business Park Zone 1, Burntwood	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.65 Mount Villa, 2 Trent Valley Road, Lichfield

ELAA ID: 64	Location: Mount Villa, 2 trent Valley road, Lichfield	Settlement: Burntwood	Ward: Stowe
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.66 Access Bookings, St Johns Street, Lichfield

ELAA ID: 65	Location: Access Bookings, St Johns Street, Lichfield	Settlement: Lichfield	Ward: Leomansly
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.67 Jervis Court, Rugeley Road, Burntwood

ELAA ID: 66	Location: Jervis Court, Rugeley Road, Burntwood	Settlement: Burntwood	Ward: Boney Hay & Central
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.68 Land at Lichfield South Business Park, Birmingham Road

ELAA ID: 67	Location: Land at Lichfield South Business Park, Birmingham Road	Settlement: Rural	Ward: Shenstone
ELAA Category: Planning Permission Full (see Table D.1 & Map 20: Wall Island (Lichfield South))			

Table D.69 Former Decades, 22 St Johns Street, Lichfield

ELAA ID: 68	Location: Former Decades, 22 St Johns Street	Settlement: Lichfield	Ward: Leomansly
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.70 Unit 1c Eastern park, Eastern Avenue, Lichfield

ELAA ID: 69	Location: Unit 1c Eastern park, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Curborough
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.71 Trent Business Centre, Eastern park, Eastern Avenue, Lichfield

ELAA ID: 70	Location: Trent Business Centre, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Stowe
ELAA Category: Complete (see Appendix C & Map 3: Lichfield City (East))			

Table D.72 The Olde Corner House, Muckley Corner

ELAA ID: 71	Location: The Olde Corner House, Muckley Corner	Settlement: Rural	Ward: Hammerwich with Wall
ELAA Category: Complete (see Appendix C & Map 19: Muckley Corner)			

Table D.73 UK Pallet Express, Wood End Lane, Fradley

ELAA ID: 72	Location: UK Pallet Express Express, Wood End Lane, Fradley	Settlement: Fradley	Ward: Alrewas & Fradley
ELAA Category: Planning Permission Full (see Appendix D.1 & Map 2: Fradley Park)			

Table D.74 19b The Close, Lichfield

ELAA ID: 73	Location: 19b The Close, Lichfield	Settlement: Lichfield	Ward: Stowe
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.75 19b Cherry Orchard, land off, Lichfield

ELAA ID: 74	Location: Cherry orchard, land off, Lichfield	Settlement: Lichfield	Ward: St Johns
ELAA Category: Complete (see Appendix C & Map 4: Lichfield City (Central))			

Table D.76 Oricia Building, Fisherwick

ELAA ID: 75	Location: Oricia Building, Fisherwick	Settlement: Rural	Ward: Whittington & Streethay
ELAA Category: Complete (see Appendix C & Map 14: Fisherwick)			

Table D.77 Former Go Bananas, Smiths Close, Burntwood Business Park Zone 3

ELAA ID: 76	Location: Former Go Bananas, Smiths Close, Burntwood Business Park Zone 3	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business park)			

Table D.78 Former Go Bananas, Smiths Close, Burntwood Business Park Zone 3

ELAA ID: 77	Location: Units A & B, Main Street, Alrewas	Settlement: Alrewas	Ward: Alrewas & Fradley
ELAA Category: Complete (see Appendix C & Map 21: Main Street, Alrewas)			

Table D.79 Shaw Lane Farm, Shaw Lane, Kings Bromley

ELAA ID: 78	Location: Shaw Lane Farm, Shaw Lane, Kings Bromley	Settlement: Rural	Ward: Armitage with Handsacre
ELAA Category: Complete (see Appendix C & Map 22: Shaw Lane, Kings Bromley)			

Table D.80 Unit 20 Cinder Road, Burntwood Business Park Zone 3, Burntwood

ELAA ID: 79	Location: Unit 29 Cinder Road, Burntwood Business Park Zone 3	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Complete (see Appendix C & Map 1: Burntwood Business Park)			

Table D.81 Land at RJK Construction, Overly Lane

ELAA ID: 80	Location: Land at RJK Construction, Overly Lane	Settlement: Rural	Ward: Alrewas & Fradley
ELAA Category: Complete (see Appendix C & Map 11: Overly Lane)			

Table D.82 Former Olaf Johnson site, Cannock Road, Burntwood

ELAA ID: 81	Location: Former Olaf Johnson site, Cannock Road, Burntwood		Settlement: Burntwood	Ward: Chasetown
SHLAA ID: 841	ELR site ID: -	Planning Ref: N/A	Source: Call for sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 2.4	Floorspace (m²): 7800	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within town centre boundary - appropriate for town centre uses. Adjacent allocated employment area. Brownfield site, possibility for contaminated land. Within Forest of Mercia area. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area.			
Available? No	Availability Notes: Planning permission granted on site for retail development (Ref:16/01379/FULM). Site therefore not available for employment development.			
Achievable? Yes	Achievability Notes: Unlikely to be developed for employment uses following grant of retail permission (subject to legal agreement).			
ELAA Category: Not Available				

Table D.83 Land off Cinder Road, Burntwood Business Park Zone 3

ELAA ID: 82	Location: Land off Cinder Road, Burntwood Business Park Zone 3	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Under Construction (see Table B.1 & Map 1: Burntwood Business Park)			

Table D.84 Units 10 and 11, Burntwood Business Park Zone 4

ELAA ID: 83	Location: Units 10 and 11, Burntwood Business Park Zone 4		Settlement: Burntwood	Ward: Chasetown
SHLAA ID: N/A	ELR site ID: P31	Planning Ref: N/A	Source: Allocated/Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 1.5	Floorspace (m²): 5375	FTE Jobs (estimate): 115	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of SSSI. Within Forest of Mercia area. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area. Adjacent to residential area.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. Promoted by landowner/agent for employment uses. ELCA notes that land owner confirms site is available for employment development and planning application being prepared with development to come forward in medium term.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Available				

Table D.85 Land off Cannel Road, Burntwood Business Park Zone 3

ELAA ID: 84	Location: Land off Cannel Road, Burntwood Business Park Zone 3	Settlement: Burntwood	Ward: Chasetown
ELAA Category: Planning Permission Full (see Table D.1 & Map 1: Burntwood Business Park)			

Table D.86 Land adjacent 39 Cannock Road, Chase Terrace, Burntwood

ELAA ID: 85	Location: Land adjacent 39 Cannock Road, Chase Terrace		Settlement: Burntwood	Ward: Chase Terrace
SHLAA ID: 496	ELR site ID: P34	Planning Ref: N/A	Source: Allocated/Call for Sites submission	Proposed use class: B1b/B1c
Site Area (Ha): 0.33	Floorspace (m²): 1073	FTE Jobs (estimate): 27	ELAA Map Ref (Appendix E): Map 1: Burntwood Business Park	
Suitable? Yes	Suitability Notes: Within Burntwood which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within 1km of SSSI. Within Forest of Mercia area. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Burntwood Neighbourhood Area. Adjacent to residential area. Site proposed to be removed from employment area and allocated for residential development through emerging Local Plan Allocations document.			

ELAA ID: 85	Location: Land adjacent 39 Cannock Road, Chase Terrace	Settlement: Burntwood	Ward: Chase Terrace
Available? No	Availability Notes: Site currently available and is being promoted by landowner/agent for residential uses. ECLA notes that site is no longer available for employment. Planning permission for residential development of site granted (ref: 17/01352/FULM). Site unlikely to be available for employment development.		
Achievable? Yes	Achievability Notes: No known constraints to achievability.		
ELAA Category: Not Available			

Table D.87 Armitage Shanks, Land at Old Road, Armitage

ELAA ID: 86	Location: Armitage Shanks, Land at Old Road, Armitage		Settlement: Armitage with Handsacre	Ward: Armitage with Handsacre
SHLAA ID: 120	ELR site ID: P35	Planning Ref: N/A	Source: Allocated/Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 2.2	Floorspace (m ²): 7848	FTE Jobs (estimate): 167	ELAA Map Ref (Appendix E): Map 10: Armitage with Handsacre	
Suitable? Yes	Suitability Notes: Within Armitage with Handsacre which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Armitage with Handsacre Neighbourhood Area. Adjacent to residential area. Adjacent to conservation area. Site proposed to be removed from employment area through emerging Local Plan Allocations document.			
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. ECLA notes that site is no longer required for business use and alternative uses have been proposed.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.88 Eastfields Farm, Alrewas Road, Kings Bromley

ELAA ID: 87	Location: Eastfields Farm, Alrewas Road, Kings Bromley		Settlement: Kings Bromley	Ward: Armitage with Handsacre
SHLAA ID: N/A	ELR site ID: P37	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 1.34	Floorspace (m ²): 1250	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 23: Alrewas Road, Kings Bromley	
Suitable? No	Suitability Notes: Outside of settlement which is not identified as a key sustainable settlement within the adopted Local Plan Strategy. Within the rural area. Greenfield site, agricultural buildings. Agricultural land classification Grades 2 and 4. Part of site within Flood Zone 2. Site is within the Cannock Chase SAC zone of influence.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			

ELAA ID: 87	Location: Eastfields Farm, Alrewas Road, Kings Bromley	Settlement: Kings Bromley	Ward: Armitage with Handsacre
ELAA Category: Not Available			

Table D.89 Land north of Bassetts Pole, Canwell

ELAA ID: 88	Location: Land north of Bassetts Pole, Canwell		Settlement: Rural	Ward: Bourne Vale
SHLAA ID: N/A	ELR site ID: P38	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 3.0	Floorspace (m²): 15,000	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 9: Bassetts Pole	
Suitable? Yes	Suitability Notes: Outside of settlement within the rural area. Greenfield site. Within Green Belt. Agricultural land classification Grade 3. TPO protected trees within site. BAS within 1km.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.90 Land west of Shenstone, Lynn Lane, Shenstone

ELAA ID: 89	Location: Land west of Shenstone, Lynn Lane		Settlement: Shenstone	Ward: Shenstone
SHLAA ID: 545	ELR site ID: P39	Planning Ref: N/A	Source: Call for Sites submission (Mixed-use proposed)	Proposed use class: B1/B2/B8
Site Area (Ha): 12.0 (50ha whole site)	Floorspace (m²): 40,500	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 7: Shenstone	
Suitable? Yes	Suitability Notes: Adjacent to Shenstone which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent allocated employment area. Greenfield site. Within Green Belt. Agricultural land classification Grades 2 & 3. Part of site within Flood Zones 2 & 3. TPO protected trees within site. BAS within 1km. Within designated Shenstone Neighbourhood Area - Shenstone Neighbourhood Plan 'made' 13 December 2016.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.91 Land south of Birchbrook Industrial Park, Lynn Lane, Shenstone

ELAA ID: 90	Location: Land south of Birchbrook Industrial Park, Lynn Lane		Settlement: Shenstone	Ward: Shenstone
SHLAA ID: 953	ELR site ID: P40	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1/B2/B8

ELAA ID: 90	Location: Land south of Birchbrook Industrial Park, Lynn Lane		Settlement: Shenstone	Ward: Shenstone
Site Area (Ha): 2.6	Floorspace (m²): 6,245	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 7: Shenstone	
Suitable? Yes	Suitability Notes: Adjacent to Shenstone which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent allocated employment area. Greenfield site. Within Green Belt. Agricultural land classification Grades 2 & 3. Part of site within Flood Zones 2 & 3. TPO protected trees within site. BAS within 1km. Within designated Shenstone Neighbourhood Area - Shenstone Neighbourhood Plan 'made' 13 December 2016.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.92 Land west of Birchbrook Industrial Park, Lynn Lane, Shenstone

ELAA ID: 91	Location: Land west of Birchbrook Industrial Park, Lynn Lane		Settlement: Shenstone	Ward: Shenstone
SHLAA ID: 953	ELR site ID: P41	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 2.34	Floorspace (m²): 8,385	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 7: Shenstone	
Suitable? Yes	Suitability Notes: Adjacent to Shenstone which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent allocated employment area. Greenfield site. Within Green Belt. Agricultural land classification Grades 2 & 3. Adjacent to Flood Zones 2 & 3. TPO protected trees within site. BAS within 1km. Within designated Shenstone Neighbourhood Area - Shenstone Neighbourhood Plan 'made' 13 December 2016.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.93 The Homestead, Haunton Road, Harlaston

ELAA ID: 92	Location: The Homestead, Haunton Road, Harlaston		Settlement: Harlaston	Ward: Mease Valley
SHLAA ID: 68	ELR site ID: P42	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1c
Site Area (Ha): 0.17	Floorspace (m²): 550	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 24: Haunton Road, Harlaston	
Suitable? Yes	Suitability Notes: Adjacent to settlement which is not identified as a key sustainable settlement within the adopted Local Plan Strategy. Greenfield site. Agricultural land classification Grade 4. Adjacent to Flood Zones 2 & 3. TPO protected trees within site. SSSI within 1km.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment uses.			

ELAA ID: 92	Location: The Homestead, Haunton Road, Harlaston	Settlement: Harlaston	Ward: Mease Valley
Achievable? Yes	Achievability Notes: No known constraints to achievability.		
ELAA Category: Not Available			

Table D.94 Dunmore Hay Lane, Fradley

ELAA ID: 93	Location: Dunmore Hay Lane, Fradley		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: 377	ELR site ID: P44	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1c
Site Area (Ha): 1.9	Floorspace (m²): 6175	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Greenfield site. Agricultural land classification Grade 3. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.95 Land north of Bassetts Pole, Canwell (2)

ELAA ID: 94	Location: Land north of Bassetts Pole, Canwell (2)		Settlement: Rural	Ward: Bourne Vale
SHLAA ID: N/A	ELR site ID: P45	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 6.4	Floorspace (m²): 32,000	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 9: Bassetts Pole	
Suitable? Yes	Suitability Notes: Outside of settlement within the rural area. Greenfield site. Within Green Belt. Agricultural land classification Grade 3. TPO protected trees within site. BAS within 1km.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.96 Land north east of Bassetts Pole, Canwell

ELAA ID: 95	Location: Land north east of Bassetts Pole, Canwell		Settlement: Rural	Ward: Bourne Vale
SHLAA ID: N/A	ELR site ID: P46	Planning Ref: N/A	Source: Call for Sites submission	Proposed use class: B1/B2/B8

ELAA ID: 95	Location: Land north east of Bassetts Pole, Canwell		Settlement: Rural	Ward: Bourne Vale
Site Area (Ha): 32.3	Floorspace (m²): 200,000	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 9: Bassetts Pole	
Suitable? Yes	Suitability Notes: Outside of settlement within the rural area. Greenfield site. Within Green Belt. Agricultural land classification Grade 3. TPO protected trees within site. BAS within site.			
Available? Yes	Availability Notes: Site currently in agricultural use. Promoted by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.97 Leavesley Group, Ryknield House

ELAA ID: 96	Location: Leavesley Group, Ryknield House	Settlement: Fradley	Ward: Alrewas & Fradley	
ELAA Category: ELAA Category: Complete (see Appendix C & Map 2: Fradley Park)				

Table D.98 Land at Easthill, Fradley

ELAA ID: 97	Location: Land at Easthill, Fradley		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P50	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B2/B8
Site Area (Ha): 5.5	Floorspace (m²): 32,894	FTE Jobs (estimate): 617	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent to allocated employment area. Greenfield site. Grade 3 agricultural land. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area. Site is proposed to be allocated for employment development within emerging Local Plan Allocations document.			
Available? Yes	Availability Notes: Site is not allocated but has been promoted through Call for Sites by landowner/agent for employment uses. Planning permission granted (ref: 17/00059/FULM).			
Achievable? Yes	Achievability Notes:			
ELAA Category: Available				

Table D.99 Fradley West, Fradley

ELAA ID: 98	Location: Fradley West, Fradley		Settlement: Rural	Ward: Alrewas & Fradley
SHLAA ID: 838	ELR site ID: P54	Planning Ref: -	Source: Call for Sites submission (Mixed-use proposed)	Proposed use class: B1/B2/B8

ELAA ID: 98	Location: Fradley West, Fradley		Settlement: Rural	Ward: Alrewas & Fradley
Site Area (Ha): 30 (90Ha whole site)	Floorspace (m²): 107,500	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent to allocated employment area. Part Brownfield part greenfield site, possibility for contaminated land. Grade 3 agricultural land. Site is within the Cannock Chase SAC zone of influence. BAS within 1km. Within designated Fradley Neighbourhood Area. Conservation Area.HS2.			
Available? Yes	Availability Notes: Site is not allocated but has been promoted through Call for Sites by landowner/agent for mixed use development including 30 hectares of employment development.			
Achievable? Yes	Achievability Notes: No known constraints to achievability. Access and transport issues would need to be considered.			
ELAA Category: Not Available				

Table D.100 Land at Common Lane, Whittington

ELAA ID: 99	Location: Land at Common Lane, Whittington		Settlement: Whittington	Ward: Whittington
SHLAA ID: 748	ELR site ID: -	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 0.78	Floorspace (m²): 2535	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 25: Common Lane, Whittington	
Suitable? No	Suitability Notes: Adjacent to Whittington which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within Green Belt. Greenfield site. Grade 2 & 3 agricultural land. Adjacent to conservation area. Site is within the Cannock Chase SAC zone of influence. TPO protected trees within site. Within designated Whittington & Fisherwick Neighbourhood Area.			
Available? Yes	Availability Notes: Site is not allocated but has been promoted through Call for Sites by landowner/agent for employment and residential uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.101 Former Norgren site, Eastern Avenue, Lichfield

ELAA ID: 100	Location: Former Norgren site, Eastern Avenue, Lichfield		Settlement: Lichfield	Ward: Stowe
SHLAA ID: 856	ELR site ID: -	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha): 4.1	Floorspace (m²): 14620	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 3: Lichfield City (East)	
Suitable? Yes	Suitability Notes: Within Lichfield which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Site is within the Cannock Chase SAC zone of influence. Within designated			

ELAA ID: 100	Location: Former Norgren site, Eastern Avenue, Lichfield	Settlement: Lichfield	Ward: Stowe
	Lichfield City Neighbourhood Area. Adjacent to residential areas. Site proposed to be removed from employment area and allocated for mixed-use residential and commercial development through emerging Local Plan Allocations document.		
Available? No	Availability Notes: Site is not allocated but has been promoted through Call for Sites by landowner/agent for a range of uses including residential and employment proposals. Site has planning permission (ref 17/00060/OUTFULM) for mixed use commercial and residential development which is under construction. Site therefore not considered to be available for employment/economic development.		
Achievable? Yes	Achievability Notes: No known constraints to achievability.		
ELAA Category: Not Available			

Table D.102 Seedy Mill Water Treatment Works, Lichfield Road

ELAA ID: 101	Location: Seedy Mill Water Treatment Works, Lichfield Road		Settlement: Rural	Ward: Longon
SHLAA ID: N/A	ELR site ID: P25	Planning Ref: -	Source: ELR	Proposed use class: B1/B2/B8
Site Area (Ha): 5.25	Floorspace (m²): 18802	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 18: Lichfield Road, Seedy Mill	
Suitable? Yes	Suitability Notes: Outside of any settlement identified as a key sustainable settlement within the adopted Local Plan Strategy. Brownfield site, possible contaminated land. Within Green Belt. Grade 3 agricultural land. Adjacent Flood Zone 2 and 3. Adjacent to conservation area. TPO protected trees within site. Site is within the Cannock Chase SAC zone of influence. BAS within 1km. Within designated Longdon Neighbourhood Area.			
Available? Yes	Availability Notes: Currently in use. Site identified through Employment Land Review so unknown if site is available.			
Achievable? Yes	Achievability Notes: Not known if current use would represent constraint to achievability.			
ELAA Category: Not Available				

Table D.103 Land north of Fradley Lane, Fradley

ELAA ID: 102	Location: Land north of Fradley Lane, Fradley		Settlement: Fradley	Ward: Alrewas and Fradley
SHLAA ID: 87	ELR site ID: P26	Planning Ref: -	Source: ELR	Proposed use class: B1
Site Area (Ha): 4.76	Floorspace (m²): 15472	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Greenfield site. Grade 3 agricultural land. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site identified through Employment Land Review so unknown if site is available for employment uses.			

ELAA ID: 102	Location: Land north of Fradley Lane, Fradley	Settlement: Fradley	Ward: Alrewas and Fradley
Achievable? Yes	Achievability Notes: No known constraints to achievability,		
ELAA Category: Not Available			

Table D.104 Land at junction of A51 and A515, Stafford Road, Lichfield

ELAA ID: 103	Location: Land at Junction of A51 and A515, Stafford Road, Lichfield		Settlement: Lichfield	Ward: Chadsmead
SHLAA ID: 671	ELR site ID: P48	Planning Ref: -	Source: ELR	Proposed use class: B1
Site Area (Ha): 3.91	Floorspace (m²): 12702	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Lichfield which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within Green Belt. Greenfield site. Grade 3 agricultural land. Site is within the Cannock Chase SAC zone of influence. BAS within 1km. TPO protected trees within site. Within designated Lichfield City Neighbourhood Area.			
Available? Yes	Availability Notes: Site identified through Employment Land Review so unknown if site is available for employment uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability,			
ELAA Category: Not Available				

Table D.105 Land south east of Bassetts Pole, Canwell

ELAA ID: 104	Location: Land south east of Bassetts Pole, Canwell		Settlement: Rural	Ward: Bourne Vale
SHLAA ID: 15	ELR site ID: P49	Planning Ref: N/A	Source: ELR	Proposed use class: B1/B2/B8
Site Area (Ha): 0.12	Floorspace (m²): 1280	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 9: Bassetts Pole	
Suitable? Yes	Suitability Notes: Outside of settlement within the rural area. Greenfield site. Within Green Belt. Agricultural land classification Grade 3. TPO protected trees within site. BAS within 1km of site.			
Available? Yes	Availability Notes: Site identified through Employment Land Review so unknown if site is available for employment uses.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.106 Land at Hilliards Cross, Fradley

ELAA ID: 105	Location: Land at Hilliards Cross, Fradley		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: P51	Planning Ref: -	Source: ELR	Proposed use class: B2/B8
Site Area (Ha): 1.63	Floorspace (m²): 17546	FTE Jobs (estimate): 365	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent to allocated employment area. Part brownfield part greenfield. Previously allocated as Hotel site. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area. Site is proposed to be allocated for employment development within emerging Local Plan Allocations document.			
Available? Yes	Availability Notes: ECLA notes that land owner suggests site is available for employment and other uses. Site has been promoted through Call for Sites and Local Plan process.			
Achievable? Yes	Achievability Notes: No known constraints to achievability. Access and transport issues would need to be considered.			
ELAA Category: Available				

Table D.107 Land west of Bonehill Mews, Lichfield Street, Fazeley

ELAA ID: 106	Location: Land west of Bonehill Mews, Lichfield Street, Fazeley		Settlement: Rural	Ward: Bourne Vale
SHLAA ID: 97	ELR site ID: P52	Planning Ref: N/A	Source: ELR	Proposed use class: B1
Site Area (Ha): 0.11	Floorspace (m²): 361	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 9: Bassetts Pole	
Suitable? Yes	Suitability Notes: Within Fazeley, Mile Oak & Bonehill which is identified as a sustainable settlement within the adopted Local Plan Strategy. Brownfield site, possibility of contaminated land. Within conservation area.			
Available? No	Availability Notes: Site identified through Employment Land Review so unknown if site is available for employment uses. Site has previously been promoted for residential uses therefore considered unlikely to be available for employment development.			
Achievable? Yes	Achievability Notes: No known constraints to achievability.			
ELAA Category: Not Available				

Table D.108 Land north of Armitage Shanks, Armitage

ELAA ID: 107	Location: Land north of Armitage Shanks, Armitage		Settlement: Armitage with Handsacre	Ward: Armitage with Handsacre
SHLAA ID: 120	ELR site ID: P53	Planning Ref: N/A	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha) 3.58	Floorspace (m²): 12793	FTE Jobs (estimate): 273	ELAA Map Ref (Appendix E): Map 10: Armitage with Handsacre	

ELAA ID: 107	Location: Land north of Armitage Shanks, Armitage	Settlement: Armitage with Handsacre	Ward: Armitage with Handsacre
Suitable? Yes	Suitability Notes: Adjacent to Armitage with Handsacre which is identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Brownfield site, possibility for contaminated land. Possible area of Coal Subsidence. Site is within the Cannock Chase SAC zone of influence. Within designated Armitage with Handsacre Neighbourhood Area. Adjacent to conservation area. TPO protected trees within site. Within 1km of BAS. Site is proposed to be removed from employment area through emerging Local Plan Allocations document.		
Available? Yes	Availability Notes: Site currently available and is allocated for employment use. ECLA notes that site is no longer required for business use and alternative uses have been proposed.		
Achievable? No	Achievability Notes: ECLA notes that there are uncertainties with regards to access to site and suggests removal from employment land capacity.		
ELAA Category: Not Available			

Table D.109 Land at Cricket Lane, Lichfield

ELAA ID: 108	Location: Land at Cricket Lane, Lichfield		Settlement: Lichfield	Ward: St Johns
SHLAA ID: 32	ELR site ID: P64	Planning Ref: -	Source: Allocated	Proposed use class: B1/B2/B8
Site Area (Ha) 13.2	Floorspace (m ²): 47300	FTE Jobs (estimate): 733	ELAA Map Ref (Appendix E): Map 5: Lichfield City (South)	
Suitable? Yes	Suitability Notes: Part of the South Lichfield Cricket Lane Strategic Development Allocation (SDA) within the adopted Local Plan Strategy. Allocated for employment uses. Greenfield site. Grade 2 agricultural land classification. Site is within the Cannock Chase SAC zone of influence. Within designated Lichfield City Neighbourhood Area.			
Available? Yes	Availability Notes: Site is allocated for employment uses within the adopted Local Plan Strategy. ECLA notes that agent confirms employment development is to be pursued with planning application being prepared.			
Achievable? Yes	Achievability Notes: No known constraints to achievability			
ELAA Category: Available				

Table D.110 Rugeley Power Station

ELAA ID: 109	Location: Rugeley Power Station		Settlement: Rural	Ward: Armitage with Handsacre
SHLAA ID: 1031 & 406	ELR site ID: -	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B1/B2/B8 (mixed use)
Site Area (Ha) 83.76	Floorspace (m ²): Unknown	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 10: Armitage with Handsacre	
Suitable? Yes	Suitability Notes: Site is located adjacent to East of Rugeley Strategic Development Allocation (SDA) and incorporates part of SDA allocated for 450 homes within the adopted Local Plan Strategy (see SHLAA site 406). Part of larger cross boundary site which includes land within Cannock Chase District. Site is adjacent to built up area of Rugeley within Cannock Chase District. Majority Brownfield site some Greenfield elements (sports pitches). Majority of site classifies as urban, part grade 3 and 4 agricultural land classification. Site is within the Cannock Chase SAC zone of influence. Within designated Armitage with Handsacre Neighbourhood Area. Likely site			

ELAA ID: 109	Location: Rugeley Power Station	Settlement: Rural	Ward: Armitage with Handsacre
	would comprise mixed use redevelopment including residential and employment uses, no information available about potential uses or split as As such no floorspace calculation has been made and the Site Area (Ha) will not be included in ELAA 2016 results (Table 5.1)		
Available? Unsure	Availability Notes: Closure of current power station has been announced. Decommissioning and demolition/remediation expected to take approximately 4 years from closure of station. Timescales and level of demolition/remediation prior to development currently unknown.		
Achievable? Unsure	Achievability Notes: Given uncertainty of closure of station and the timescales of the site becoming available there is uncertainty over the achievability of the site,		
ELAA Category: Uncategorised ^(vi) - not enough information currently to categorise site as either 'available' or 'not available'. Site is likely to become available for development within the plan period, however the mix/scale of development and timescales are currently unknown. As such floorspace not included in results of assessment at this stage.			

Table D.111

ELAA ID: 110	Location: Land south of Fradley South	Settlement: Fradley	Ward: Alrewas & Fradley	
SHLAA ID: 132	ELR site ID: -	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B1/B2/B8/Residential
Site Area (Ha) 3.9	Floorspace (m²): 13975	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley park	
Suitable? No	Suitability Notes: Within Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Within allocated employment area. Site is allocated as protected open space to provide separation between adjacent employment and residential uses. Brownfield site, possibility for contaminated land. Grade 3 agricultural land. BAS within 1km. Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? No	Availability Notes: Site has been promoted for residential development. Unlikely to be available for employment uses. Site is allocated as protected open space.			
Achievable? Yes	Achievability Notes: No known constraints to achievability			
ELAA Category: Not Available				

Table D.112

ELAA ID: 111	Location: Land area of Wellington Crescent, Fradley	Settlement: Fradley	Ward: Alrewas & Fradley	
SHLAA ID: N/A	ELR site ID: -	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B2/B8
Site Area (Ha): 7.9	Floorspace (m²): 27,950	FTE Jobs (estimate): 569	ELAA Map Ref (Appendix E): Map 2: Fradley Park	

vi Not enough information to assess if 'available' or 'not available' at this stage. Site is likely to become available within plan period however the mix/scale of uses proposed and more definitive timescales are currently unknown. However, it is considered inappropriate to categorise the site as 'not available' given the staged landowner intentions and the generally supportive context for redevelopment of the site (taking into account the adjacent redeveloped site of the former Power Station A)

ELAA ID: 111	Location: Land area of Wellington Crescent, Fradley	Settlement: Fradley	Ward: Alrewas & Fradley
Suitable? Yes	Suitability Notes: Adjacent to Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent to allocated employment area. Greenfield site. Grade 3 agricultural land. Site is within the Cannock Chase SAC zone of influence. Within designated Streethay Neighbourhood Area. Site is proposed to be allocated for employment development within emerging Local Plan Allocations document.		
Available? Yes	Availability Notes: Site is not allocated but has been promoted through Call for Sites by landowner/agent for employment uses.		
Achievable? Yes	Achievability Notes: No known constraints to achievability.		
ELAA Category: Available			

Table D.113


ELAA ID: 112	Location: Midlands Go Kart, Wood End Lane, Fradley		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: -	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 0.9	Floorspace (m ²): 3128	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. Adjacent to allocated employment area. Brownfield site currently in commercial use (Go Kart track). Site is within the Cannock Chase SAC zone of influence. Within designated Fradley Neighbourhood Area.			
Available? Yes	Availability Notes: Site is not allocated but has been promoted through Call for Sites and Local Plan Allocations consultation by landowner/agent for employment uses. Site is currently in use for alternative use.			
Achievable? Yes	Achievability Notes: No known constraints to achievability. Access and transport issues would need to be considered.			
ELAA Category: Not Available				

Table D.114

ELAA ID: 113	Location: Orchard Farm, Fradley		Settlement: Fradley	Ward: Alrewas & Fradley
SHLAA ID: N/A	ELR site ID: -	Planning Ref: -	Source: Call for Sites submission	Proposed use class: B1/B2/B8
Site Area (Ha): 10.04	Floorspace (m ²): 35,475	FTE Jobs (estimate): -	ELAA Map Ref (Appendix E): Map 2: Fradley Park	
Suitable? Yes	Suitability Notes: Adjacent to Fradley Park which is adjacent to Fradley identified as a key sustainable settlement within the adopted Local Plan Strategy. A Greenfield site. Grade 3 agricultural land. Site is within the Cannock Chase SAC zone of influence. Within designated Streethay Neighbourhood Area.			
Available? No	Availability Notes: Site is not allocated but has been promoted through Call for Sites by landowner/agent for employment uses. Site currently in alternative use as go kart track, unlikely to be available for development in short term.			

Employment Land Availability Assessment Maps

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No. 100017765

Map 1: Burntwood Business Park

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorized | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No. 100017765

Map 2: Fradley & Fradley Park

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright, Database Rights 2018, Lichfield District Council, Licence No. 100017765

Map 3: Lichfield City (East)

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright, Database Rights 2018, Lichfield District Council, Licence No: 100017765

Map 4: Lichfield City (Central)

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright, Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 5: Lichfield City (South)

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



Map 6: Lichfield City (North)

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 7: Shenstone

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 8: Fazeley, Mile Oak & Bonehill

ELAA Sites 2017-2018


- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

NOT TO SCALE

Lichfield
district council
www.lichfielddc.gov.uk



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



Map 9: Bassetts Pole


NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 10: Armitage with Handsacre

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorized | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 1000177657

Map 11: Overly Lane, Alrewas Parish

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

NOT TO SCALE

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765


Map 12: Croxall Road, Alrewas Parish

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 13: Asby Road

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



Map 14: Fisherwick

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 15: Birmingham Road

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright, Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 16: Trent Valley Trading Estate

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

NOT TO SCALE

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 17: Jerrys Lane

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 18: Lichfield Road, Seedy Mill

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 19: Muckley Corner

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



Map 20: Wall Island (Lichfield South)

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 21: Main Street, Alrewas

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorized | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765


Map 22: Shaw Lane, Kings Bromley

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorized | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 23: Alrewas Road, Kings Bromley

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorized | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 24: Haunton Road, Harlaston

NOT TO SCALE


ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N

No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 25: Common Lane, Whittington

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorised | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk



No decision has been taken to allocate these sites. The inclusion of any site in this assessment does not indicate that it will be allocated or successfully obtain permission for development.



© Crown Copyright. Database Rights 2018. Lichfield District Council. Licence No: 100017765

Map 26: Park Lane, Elmhurst

NOT TO SCALE

ELAA Sites 2017-2018

- | | | |
|---------------|---------------------------------------|---|
| Complete | Site with planning permission | Proposed for allocation in emerging LPA |
| Available | Site under construction | Green Belt Site |
| Not Available | Site allocated for employment use | Settlement Boundary |
| Uncategorized | Site with expired planning permission | District Boundary |
| | Site submitted via 'Call for Sites' | |

Lichfield
district council
www.lichfielddc.gov.uk

N